


# INSTALL INSTRUCTIONS



If YOU can IMAGINE it... WE can BUILD it

# TECTRAC™ SK

# WARNING!

The safe installation and use of commercial tenting products can vary from site to site and during varying climactic conditions. Careful consideration should be paid to any installation during windy conditions and shall be monitored throughout the duration of the installation. Periodic maintenance and monitoring of the installation by the installer is required. Techniques other than those specified in this document may be required during these types of conditions.

Users and installers shall indemnify and hold harmless Aztec Tent for any claim resulting from the improper installation and/or maintenance of this unit.

Soil conditions also vary from site to site. The included anchoring package for this tent may need to be supplemented with alternate anchoring during windy conditions and in areas with questionable soil holding power. Full product engineering may be available.

# NOTICE

This tent product is not intended to be used as a shelter from severe weather. Aztec assumes no liability for such use. An evacuation plan for the area covered within this tented space is imperative and shall be thoroughly posted for all users and potential occupants of the tent. Severe weather including electrical storm systems, moderate to severe wind, heavy rains, snow, or any condition that raises any doubt to the structural integrity of the tent are immediate signs that an evacuation is necessary. Severe bodily injury and/or death can occur.

The installation of electrical, plumbing, lighting, appliances and/or HVAC equipment are not covered within this manual. Users/Installers shall follow local code requirements for the installation of these items using certified personnel. Aztec Tents shall be indemnified and held harmless from any such use or injury resulting from its use.

## \*\*\*IMPORTANT SAFETY INFORMATION\*\*\*

Proper personnel safety equipment should be worn at all times during the installation of any tenting products.

Hard Hat


Safety Glasses

Work Gloves

Long Pants

Steel Toe Boots

OSHA Approved Harness and restraint system (for off ground activities)



Thank you for your recent purchase from Aztec Tents. The following procedures will help you through your installation. If you ever run into problems with the installation of your Aztec Tent give one of our sales/service professionals a call. A complete listing of sales, service, and operational support is always available on our website at [www.aztectents.com](http://www.aztectents.com).

# Contents

Install Procedures-	4-15
Beam Components	16-17
Hardware Components	18-19
Exploded Isometric Parts Listing	20
Fabric Components	21
10' Wide Diagrams	22-23
15' Wide Diagrams	24-25
20' Wide Diagrams	26-27
30' Wide Diagrams	28-29
40' Wide Diagrams	30-31
50' Wide Diagrams	32-33
Beam Assembly Detail Drawings	34-37
Engineering Load Data	38
Parts Listing	39

## Questions? Call us.

### **Aztec Tents**

2665 Columbia Street  
Torrance, CA 90503 USA  
Direct (310) 347-3010  
Toll Free (800) 228-3687  
Fax (310) 381-0722

# Installation

## Step 1:

### Baseplate Layout

A. Determine where you would like the first corner of the structure and work from this point. It is recommended and helpful to perform a site survey, and a proposed layout drawing, prior to the first set-up at a location.

B. Establish the first baseline of either an end or one side which will serve in squaring of the following baseplates. Refer to the following diagrams to check and verify diagonals for squareness.



C. Place a registration pins (not included) or mark through the registration hole on the ground. The Tectrac Baseplates are designed with a 3/8" layout registration hole. Using a 5/16"x 6" dowel or steel rod (a sharpened pencil works nicely in soil or a large nail for pavement) and a measuring tape to mark the baseplate locations. The baseplates need to be accurately placed within a quarter of an inch in order to avoid problems with the fabric and frame installation. The base plate location points can be placed prior to unloading of the equipment.





D. From each corner mark stretch a tight straight line (not included) to the next corner and use this line to align the baseplates. Check the accuracy of "on center" placement and squareness before final anchoring.

E. Stake or Anchor Baseplates along with corresponding high wind guy points as dictated by site requirements.

Note: The recommended location for HWGuy (High Wind Guy Kit) points are straight out from all Eave Plates and should be set at a 45 degree angle. Soil conditions vary as well as the required loads for different application conditions. Refer to the engineering parameters for the Width / Configuration being used. (see Engineering Load Data)

F. Be aware of any grade variations and level any that exceed 4-5 inches between baseplates. Optional Adjustable Baseplate Inserts and 2' leg extension are available to compensate for uneven site conditions.






Step 2:

Positioning of parts for assembly

A. Determine the tilt-up plan for the layout of parts in order/direction needed by the site. (See illustration)  
This application shows for a minimal space setup so that beams are assembled in the direct workspace. Although this illustration shows the tilting of the last beam in an opposite direction and the first three beams, you can certainly tilt all beams in the same direction if you have enough space on your site.

B. Layout the frame parts (oriented to complement your plan to tilt the beams in position)

- 1st Eave Assemblies
- 2nd Beam Straight Section(s) if required
- 3rd Apex Assemblies
- 4th Purlins, Cables, & End Column Hardware
- 5th Leg Assemblies



**Step 3:**

**Connect the beam components to form the beam**


**A.** Start with the Eave Assembly of a beam and insert the Base Insert Assembly into the bottom of the beam. Remove the shackles that are already attached to the baseplate. Align the hole on the Base Insert Assembly with the corresponding hole on the baseplate and connect one shackle through both holes to allow the eave assembly to pivot on the shackle pin. **\*\*Be sure that the Base Insert Flange falls on the inside of the flange of the baseplate.**

**B.** Work from the Eave Assembly through the straights to the apex and back toward the opposing Eave Assembly connecting the beam sections together.

**C.** Insert and connect the other Base Insert Assembly and connect to the beam assembly to the baseplate as shown in part "A". **\*\*Be sure that the Base Insert Flange falls on the inside of the flange of the baseplate.**

**D.** Attach the pivot end of apex/ridge purlin with the pin to lower Purlin Plate of the Apex Assembly. Make sure that Drop-in End of Top Purlin also has the drop in cup facing down. The Gable Column Top Insert is also attached at this time to the Apex Assemblies on each end beam and additionally to any beam sets where internal divider walls are planned.

**E.** Connect the Assembly Cables to the corresponding Eave Assemblies of assembled the beams at the Universal Bracket with the 3/8" Square Bail Pin through the cables eyelet. **\*\*Make sure that the 3/8" pins are installed so that the Pin head faces to the outside of structure.**




**Step 4:**

A. Attach the Cable Bracing sets (50x blue, 40x green, 30x blue) with shackle end of cable assembly at inner faces (4 places) of first bay's Apex Assembly at the Purlin Bracket shackle tabs.

B. Attach the Middle Cable Bracing sets (50x only -white) Shackle end of cable assembly at inner faces (4 places) of first bay's Straight Beam Assembly Shorts at the lower shackle tabs of Purlin Brackets.

Note: Always connect the shackle's screw pin thread side up/out to prevent interference with fabric panels. Turnbuckles are always put at a lower position to make them more accessible for ease of adjustment.



**Step 5:**


**First Bay Beam Set Tilt-up, Top Cable Brace, and Rack to Square**

A. Tilt-up/pivot the 1st beam arch while pushing up with the ridge purlin. When the beam reaches vertical, pin Base Insert to the baseplate with the additional shackle from Step 3A as a temporary locked upright attachment with the ridge purlin acting as third point stabilizer.

B. Repeat the same process for the 2nd beam.

C. Using the Purlin Lift Tool, lift the articulating purlin which is connected to the 1st beam apex into position to "Drop-In" and connect the the 2nd beam apex. Use the safety pin to secure the purlin to the apex at this time.


D. Place additional purlins at Eave Assembly and then at Middle Purlin Positions (50x application only). Attach cable bracing turnBuckle ends to their respective upper shackle tabs, and uniformly tension to rack beams to vertical plumb. The cables should not be tightened beyond a light non-sagging tension.






Step 6:

- A. Tilt-up the next beam arch
- B. Secure Base Insert to baseplate with shackle
- C. Install Ridge Purlin and other Purlins
- D. Continue by repeating Step 6-A through 6-C with each additional beam arch



Step 7:

- A. Tilt the last beam into position using the purlin fork to assist in pushing up the beam.
- B. Secure Base Insert to baseplate with shackle
- C. Install Ridge Purlin and other Purlins



Step 8:


A. Open the Gable Panel onto drop cloth. Orient the panels with the hardware and wall snap line facing to the inside of structure. Find the Keder at end at the middle near to velcro closure portion of the panel near small "D" ring fixture.

B. Attach Pull-in Rope at small "D" ring fixture along Keder and start feeding the panel from the end at velcro middle point into the LOWER Keder track flare just above the bend of the Eave Assembly. The rope should be pulled over the Top Purlin and is used as a method of pulling from the ground from the opposite side.

Note of Caution: This method must be used prior to installing the adjacent main panel where the Gable End / Divider Panel is to be placed. The rope can abrade and burn the Roof Panel at the Top Purlin. On smaller structures the rope is not required as the height is at a workable level while standing on the ground

C. The apex portion of the Gable End / Divider Panel's Keder must be carefully hand fed about 4" at a time for 3-4 feet.

D. The bottom section of the Gable Panel's Keder has a curve, which matches the shape of the Eave Assembly. These are then fed back down into the track from the "flared" position of the Eave Assembly.




## Step 9:

A. Open the fan folded Main Panel onto drop cloth along the length of the first bay at the eave. Orient the panels curved valance edge with the hardware and wall snap line facing down to inside of tent. Position pull-in ropes in place. Snap Keder Leader to "D" ring fixture at Keder notch. Feed Keder Leader into Eave UPPER Keder track flare for both tracks of beam sets. Snap ropes to Keder Leaders. One end of the Eave Purlins can be dropped out of this bay while Main Panel is being pulled to make panel feed and pull-in easier. The ropes are placed over the Top Purlin for the pull-in from the ground on the opposite side. The Beam Cover(s) can be pulled over along with the Main Panel by simply tying the webbing tails to the Main Panel's "D" ring(s).

B. Insert Main Panel at notch with valance folded back on top of Main Panel into track about 4" past flare. Repeat this on the opposite side of Main Panels. Feed the folded portion of the Main Panel by hand until the end of the valance has advanced past the Keder track flare.

C. Two people shall help feed the panel into the channel as it is pulled to keep the fabric from jamming in the flared opening.

D. Two people pull from opposite side **EVENLY** using pull-in ropes. Continuous pulling works best opposed to 1-2-3 "Yank". Observe the position of ends being pulled, in relationship to the same points on each of the beam as this should be even. Pull the ends of Main Panel straight out of upper Keder track flare at the opposite Eave Assembly, continue pulling until Main Panel is centered. The top edge of internal wall snap line flap and Main Panel valance assembly should be even with the Eave Purlin Bracket. Feed the remaining panel ends into the curved portion of the Eave Assemblies down from the flared opening to the Purlin Bracket at eave. Replace the Bottom Purlins at this time and pull the Main Panels valances the rest of the way down.



Step 10:

A. Attach the canopy jacks at the lower fixture shackle on the Outer Eave Plate and remove the temporary loose-pinned 5/8" shackles at Baseplates along the side to be lifted.

\*\* Jacks should be placed per diagram and used in a coordinated fashion. Maintain even and level lifting of the frame to avoid damage of the parts at the connection points.


B. Lift each beam in a coordinated manor. Be aware that the frame will spring out 3" to 4" (this is normal) and be stopped by the Assembly Cables. Press the double button pin at the bottom of Eave Assembly allowing the Baseplate Insert to be removed. Transfer it to the bottom of leg and connect to the bottom of the Leg Assembly.

C. Continue the lift up to the 6' 10" (8' 10" for 10" legs) lift height to clear the Leg Assembly which will allow its insertion of the leg into the bottom of the Eave Assembly. Use one person on the jack, while one person inserts the Leg Assembly.

\*\*Never leave a jack unattended while supporting a load.

D. Lower the jacks and secure the Base Insert Assembly to the Baseplate with 2 shackles. Use one person on the jack and second person to manipulate the Baseplate Insert at bottom of Leg Assembly to inside face of Baseplate and align the Baseplate Insert's holes with Baseplate's holes.

Note: Pulling down on the Assembly Cable will draw Leg Assembly to correct inside position of Baseplate. (see illustration D)



**Step 11:**

**A.** Attach the canopy jacks at lower fixture shackle on Outer Eave Plate and remove the temporary loose-pinned 5/8" shackles at Baseplates along the side to be lifted.


**\*\*** Jacks should be placed per diagram and used in a coordinated fashion. Maintain even and level lifting of the frame to avoid damage of the parts at the connection points.

**B.** Lift each beam in a coordinated manor. Be aware that the frame will spring out 3" to 4" (this is normal) and be stopped by the Assembly Cables. Press the double button pin at the bottom of Eave Assembly allowing the Baseplate Insert to be removed. Transfer it to the bottom of leg and connect to the bottom of the Leg Assembly.

**C.** Continue the lift up to the 6' 10"(8' 10" for 10" legs) lift height to clear the Leg Assembly which will allow its insertion of the leg into the bottom of the Eave Assembly. Use one person on the jack, while one person inserts the Leg Assembly.  
**\*\***Never leave a jack unattended while supporting a load.

**D.** Lower the jacks and secure the base Insert Assembly to the Baseplate with 2 shackles. Use one person on the jack and second person to manipulate the Baseplate Insert at bottom of Leg Assembly to inside face of Baseplate and align the Baseplate Insert's holes with Baseplate's holes.

**E.** Install and connect cross cables in the wall area. Connect shackled end of the cable to the Purlin Bracket Plate just under the eave purlin with the 3/8" Shackle. Connect the turnbuckle end of the cable assembly to the 5/8" Shackle of the opposing baseplate. You can now fully tension the cable sets in both the roof and the wall area watching that you tension them evenly to set the beams in a vertical position.



**Step 12:**

**Installation of HWK-High Wind Guy-out (when required)**


**A.** Attach 2" x 20'0" Web Strap w/ Hook/ to the 3/8" Shackle on Outer Eave Plates of each Eave Assembly

**B.** Position the HWK- Ratchet on the ground at a distance equal to the height of the connection point to the structure. For 8' legs this will be 8' from the baseplate, and 10' from the baseplate for 10' legs.

**C.** Anchor the HWK-Ratchet to the ground

**D.** Put light tension into the HWK- ratchets on both sides of a given Beam Set so as not to skew the frame.

**Note:** The recommended location for HWK Guy point is straight out and down from the Outer Eave Plates at a 45-degree angle. Soil conditions will vary as well as the required loads for different configurations, see Engineering Load Specifications for resistance loading, and refer to the engineering parameters for the width being used.



**Step 13:**

**Install Gable End Upright Hardware**

**A.** Slide the Gable End Column Straight Beam (Short -30x 40x) or Straight Beam (Long -50x) up onto the Gable Column Top Insert Assembly.

**B.** Once inserted, tip the Gable End Column Straight inward to give clearance for the insertion of the Gable End Column's leg assembly including the Gable Column Base Insert Assembly

**C.** Slide the Gable Column upward on the Gable Column Top Insert allowing the Gable End Column Assembly to be swung into place on the Baseplate and be secured with the two 5/8" shackles.


## Step 14:

### Wall Installation & Removal of Assembly Cables

A. The wall is installed from the ground at the leg flares into the outer keder track (the same track used by the roof panel. The inner track can also be utilized if liner is not used). The wall panel is fed upward leading with the hook side of the wall. As with the roof panels, pull the walls upward evenly to prevent jamming. The top (snap edge) is pushed up to the flap on the roof panel containing the wall rope snap line.

B. Use a ladder to attach the the wall snaps to the snap line which is found under the wall valance flap. A tension buckle strap is provided at the upper corners. Loop the tension buckle straps through the 3/8" shackle provided below the Eave Assembly's Purlin Bracket and buckle snugly. From this position while on the ladder the Assembly Cables can be unpinned from Eave Assembly's Bracket.


C. The remaining bottom half of the wall is now fed down from wall flares to the ground level. A tension buckle strap is provided at the lower corners. Loop the tension buckle straps through the 5/8" shackle on either side of the Baseplate. Assembly and buckle snugly so the wall Keder is in tension.




## Step 15:

A. Attach 2" Webbing "V-Strap" hooks to the tensioning rings of the roof panels and gables. One (1) "V" strap with two hooks will grab the adjoining rings of adjacent panels. Insert the hook end of the 2" Ratchet with hook into the hole under the outside center edge of the Base Insert Assembly. Thread the loose end of the 2" "V-Strap" into the ratchet, pull through as tight as you can by hand and then engage the ratchet to provide slight tension.

B. Once all the tensioning ratchets are connected, you can go back and fully tension all of the ratchets around the perimeter of the tent structure,









# Beam Components



- A APEX ASSY.
- B EAVE ASSY.
- C LEG 2' EXTENSION BEAM ASSY.
- D LEG BEAM ASSY.
- E STRAIGHT BEAM (SHORT - 20X, END COL.30X,40X) 5'-3 7/8"
- F BASE 2' ADJUSTABLE INSERT (SIDE LEG)
- G TOP INSERT ASSY.
- H LEG BEAM ASSY. (END COL.)
- I BASE INSERT ASSY.
- J BASE PLATE ASSY.
- K BASE 2' ADJUSTABLE INSERT (END COL.)




# Beam Components




- A STRAIGHT BEAM (LONG) 10'-7 11/16"
- B STRAIGHT BEAM ASSY. (SHORT - 50X) 5'-3 7/8" W/ PURLIN BRKT.S
- C STRAIGHT BEAM ASSY. (SHORT) 5'-3 7/8" W/ INSERT
- D STRAIGHT BEAM (SHORT - 20X, END COL. 30X, 40X) 5'-3 7/8"
- E STRAIGHT BEAM (SHORT - 15X, END COL.3) 2'-7-15/16"

# Hardware Components




# Hardware Components




ASSEMBLY CABLE (Y)  
COLOR CODES


COLOR	BEAM SET	LENGTH
RED	10'	8'-6 1/4"
ORANGE	15'	13'-6 1/4"
YELLOW	20'	18'-6 1/4"
BLUE	30'	28'-6 1/4"
GREEN	40'	38'-6 1/4"
WHITE	50'	48'-6 1/4"




# Exploded Isometric Parts Listing




# Fabric Components




TECTRAC SK\10x10x10 SK		013008 1720	CHECKED -	DATE 01/30/08	TCSK	AZ-10108-TECTRAC	REV 0
ENGINEER CM		2665 COLUMBIA ST. TORRANCE, CA. 90503	2665 COLUMBIA ST. TORRANCE, CA. 90503	(800) 228-3687 - FAX (310) 381-0722	DRAWN KT	PART DESCRIPTION	SIZE
ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL AND INFORMATION IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.		AZTEC		CENTER CLEAR STRUCTURE / STANDARD 10' W x 10' L x 8' LEG			
TECTRAC SK							




SIDE ELEVATION



PLAN ELEVATION



ISOMETRIC ELEVATION




FRONT ELEVATION

K:\cad files\Structures\TecTrac SK\10x10x10 SK.dwg, 1/30/2008 5:22:18 PM, pdfFactory.pcc3


TECTRAC SK\10x10x20 SK		02/06/08 1050	CHECKED -	DATE 12/04/06	TCSK	AZ-10208-TECTRAC	1
ENGINEER CM		DATE 12/04/06	DATE 12/04/06	DATE 12/04/06	DATE 12/04/06	DATE 12/04/06	DATE 12/04/06
DRAWN KT		2665 COLUMBIA ST. TORRANCE, CA. 90503	(800) 228-3687 - FAX (310) 381-0722	PART DESCRIPTION			
AZTEC		CENTER CLEAR STRUCTURE / STANDARD					
AZTEC		10' W x 20' L x 8' LEG					
AZTEC		DRAWING NUMBER					
AZTEC		REV					

ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION CONTAINED HEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DEVELOPED.


PLAN ELEVATION




SIDE ELEVATION




FRONT ELEVATION




ISOMETRIC ELEVATION




TECTRAC SK\15x15x15x8 SK		02/07/08 1440	CHECKED -	DATE 02/07/08	TCSK	AZ-15158-TECTRAC	REV 0	
 2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		ENGINEER CM DRAWN KT		PART DESCRIPTION CENTER CLEAR STRUCTURE / STANDARD SIZE 15' W x 15' L x 8' LEG				ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL AND INFORMATION IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.


TECTRAC SK




SIDE ELEVATION



PLAN ELEVATION




ISOMETRIC ELEVATION




FRONT ELEVATION




TECTRAC SK\15x15x65x8 SK		02/07/08 1440	02/07/08	CM	KT	TCSK	AZ-15658-TECTRAC	0
ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL AND INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN ARE RESERVED. BY ACCEPTING THIS MATERIAL AND INFORMATION CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.		2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		AZTEC		CENTER CLEAR STRUCTURE / STANDARD 15' W x 65' L x 8' LEG		
ENGINEER	CHECKED	DATE	DRAWN	PART DESCRIPTION	CODE	SIZE	DRAWING NUMBER	REV




SIDE ELEVATION



PLAN ELEVATION



ISOMETRIC ELEVATION




FRONT ELEVATION


K:\cad files\Structures\TecTrac SK\15x15x65 SK.dwg, 2/7/2008 2:39:28 PM, pdfFactory.pc3

TECTRAC SK\20x\20x40x8 SK		020306 1045	CHECKED -	DATE 02/03/06
ENGINEER CM		DRAWN KT	AZTEC 2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722	
PART DESCRIPTION		CODE	SIZE	DRAWING NUMBER
CENTER CLEAR STRUCTURE / STANDARD			20' W x 40' L x 8' LEG	REV
TECTRAC SK		TCSK AZ20408-TECTRAC 0		


ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL AND INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DEWEAVED.




SIDE ELEVATION




PLAN ELEVATION




ISOMETRIC ELEVATION




FRONT ELEVATION


TECTRAC SK \20x\20x60x8 SK		020306 1045	CHECKED -	DATE 02/03/06
TCSK		AZ-20608-TECTRAC	ENGINEER CM	DRAWN KT
PART DESCRIPTION		CODE	SIZE	DRAWING NUMBER
CENTER CLEAR STRUCTURE / STANDARD			20' W x 60' L x 8' LEG	REV 0
 490 ALASKA AVE. TORRANCE, CA 90503 (800) 228-3687 - FAX (310) 381-0722		ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.		




TECTRAC SK\30x\30x40x8 SK		020606 1225	CHECKED -	DATE 02/06/06	TCSK	AZ-30408-TECTRAC	0
AZTEC		ENGINEER CM 2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722			DATE 02/06/06	DRAWN KT	
TECTRAC SK		PART DESCRIPTION CENTER CLEAR STRUCTURE / STANDARD 30" W x 40" L x 8" LEG			SIZE	CODE	REV
DRAWING NUMBER		REV		ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED. AND ALL RIGHTS THEREIN INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED HEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS. EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DRAWN.			




SIDE ELEVATION



PLAN ELEVATION



ISOMETRIC ELEVATION



FRONT ELEVATION

TECTRAC SK\30x\30x60 SK  
 020606 1310  
 CHECKED -  
 ENGINEER CM  
 DRAWN KT  
 DATE 07/06/06

490 ALASKA AVE. TORRANCE, CA. 90503  
 (800) 228-3887 - FAX (310) 381-0722


ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECEIPT, RESERVATION, AND INFORMATION ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS. EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.

TECTRAC SK


CENTER CLEAR STRUCTURE / STANDARD  
 30' W x 60' L x 8' LEG

REV	DRAWING NUMBER	CODE	SIZE
0	TECTRAC 0		


TCSK | AZ30608-TECTRAC 0




PLAN ELEVATION



SIDE ELEVATION



FRONT ELEVATION




ISOMETRIC ELEVATION


TECTRAC SK\40x\40x60 SK		02/07/06 1550	CHECKED -	DATE 07/20/05
ENGINEER CM		DATE 07/20/05	DRAWN KT	
PART DESCRIPTION		CODE	SIZE	DRAWING NUMBER
CENTER CLEAR STRUCTURE / STANDARD			40' W x 60' L x 8' LEG	REV
TECTRAC SK		TCSK AZ40608-TECTRAC 1		

ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL. INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.


490 ALASKA AVE. TORRANCE, CA 90503  
 (800) 228-3687 - FAX (310) 381-0722  
**AZTEC**




PLAN ELEVATION



SIDE ELEVATION



FRONT ELEVATION




ISOMETRIC ELEVATION

TECTRAC SK\40x\40x80 SK		020706 1420	CHECKED -	DATE 02/07/06
TCSK		AZ-40808-TECTRAC	ENGINEER CM	DRAWN KT
REV	DRAWING NUMBER	SIZE	CODE	PART DESCRIPTION
0				CENTER CLEAR STRUCTURE / STANDARD 40" W x 80" L x 8" LEG


ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL AND INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.

490 ALASKA AVE. TORRANCE, CA. 90503  
(800) 228-3687 - FAX (310) 381-0722  
**AZTEC**


TECTRAC SK




SIDE ELEVATION



PLAN ELEVATION




ISOMETRIC ELEVATION




FRONT ELEVATION


TCTRAC SK \50x\50x60 SK		020906 1240	02/09/06	DATE	KT	CM	ENGINEER
TCSK		AZ50608-TECTRAC	0	REV	PART DESCRIPTION		
50' W x 60' L x 8' LEG		CENTER CLEAR STRUCTURE / STANDARD			AZTEC		
490 ALASKA AVE. TORRANCE, CA. 90503		(800) 228-3687 - FAX (310) 381-0722			ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL, CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.		




SIDE ELEVATION




PLAN ELEVATION



ISOMETRIC ELEVATION




VIEW A-A




VIEW B-B




TCTRAC SK \50x\50x100 SK		020706 1430	CHECKED -	DATE 02/07/06	TCSK	AZ501008 - TCTRAC	REV 0
AZTEC		ENGINEER CM		DRAWN KT	PART DESCRIPTION		
490 ALASKA AVE. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		CENTER CLEAR STRUCTURE / STANDARD			50' W x 100' L x 8' LEG		
ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED, BY ACCEPTING THIS MATERIAL. INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED THEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DELIVERED.		TCTRAC SK					




SIDE ELEVATION




PLAN ELEVATION



ISOMETRIC ELEVATION




VIEW A-A



VIEW B-B


ITEM	QUANTITY	DWG. NO.	DESCRIPTION
1	2	TCSK3109	BASE PLATE
2	2	TCSK3110	BASE INSERT
3	1	TCSK3100	APEX ASSY.
4	2	TCSK3102	LEG ASSY.
5	2	TCSK3114	SHORT STRAIGHT (w/o INSERT) ASSY.
6	2	TCSK3101	EAVE ASSY.
7	1	TCSK3063-20'	ASSY. CABLE (18'-8 1/4") YELLOW




TECTRAC SK		PART DESCRIPTION		ENGINEER	CHECKED	DATE	PROJECT
CENTER CLEAR STRUCTURE / STANDARD		TCSK AZ-20' WIDE-PROFILE		CM	-	02/02/06	TECTRAC SK\ASSEMBLES\20 SK 121008 1715
20' WIDEX 8' LEG BEAM PROFILE		CODE	SIZE	DRAWN	KT		
DRAWING NUMBER		REV		2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE PRESERVED. BY ACCEPTING THIS MATERIAL AND INFORMATION AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, NOR ITS CONTENTS REVEALED IN ANY MANNER TO OTHERS. EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DEWEED.	

TECTRAC SK ASSEMBLES\30 SK		121008 1645	CHECKED -	DATE 02/02/06	TCSK	AZ-30' WIDE-PROFILE	REV 1
AZTEC		ENGINEER CM		DRAWN KT	PART DESCRIPTION		
2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		CENTER CLEAR STRUCTURE / STANDARD 30' WIDEX 8' LEG BEAM PROFILE			CODE	SIZE	DRAWING NUMBER
ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL AND INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN ARE RESERVED. THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DEVELOPED.							

ITEM	QUANTITY	DWG. NO.	DESCRIPTION
1	3	TCSK3109	BASE PLATE
2	2	TCSK3110	BASE INSERT
3	1	TCSK3100	APEX ASSY.
4	2	TCSK3105	LONG STRAIGHT
5	3	TCSK3102	LEG ASSY.
6	1	TCSK3114	SHORT STRAIGHT (w/o INSERT) ASSY.
7	2	TCSK3101	EAVE ASSY.
8	1	TCSK3113	END COLUMN BASE INSERT
9	1	TCSK3112	END COLUMN TOP INSERT



ITEM	QUANTITY	DWG. NO.	DESCRIPTION
1	3	TCSK3109	BASE PLATE
2	2	TCSK3110	BASE INSERT
3	1	TCSK3100	APEX ASSY.
4	2	TCSK3105	LONG STRAIGHT
5	3	TCSK3102	LEG ASSY.
6	2	TCSK3103	SHORT STRAIGHT ASSY.
7	2	TCSK3101	EAVE ASSY.
8	1	TCSK3113	END COLUMN BASE INSERT
9	1	TCSK3112	END COLUMN TOP INSERT
10	1	TCSK3114	SHORT STRAIGHT (w/o INSERT) ASSY.



TECTRAC SK ASSEMBLIES\40 SK 031308 1330		CHECKED	-	DATE	02/02/06
ENGINEER		CM	DATE	02/02/06	KT
2665 COLUMBIA ST. TORRANCE, CA. 90503 (800) 228-3687 - FAX (310) 381-0722		AZTEC			
PART DESCRIPTION		CODE	SIZE	DRAWING NUMBER	
CENTER CLEAR STRUCTURE / STANDARD				40' WIDE X 8' LEG BEAM PROFILE	
REV		1			

ALL DATA AND INFORMATION CONTAINED IN OR DISCLOSED BY THIS DOCUMENT IS CONFIDENTIAL AND PROPRIETARY. THE RECIPIENT AGREES THAT THIS MATERIAL AND INFORMATION ARE EXPRESSLY RESERVED. BY ACCEPTING THIS MATERIAL INFORMATION OF AZTEC TENTS AND ALL RIGHTS THEREIN CONTAINED HEREIN IS HELD IN CONFIDENCE AND IN TRUST AND WILL NOT BE COPIED, REPRODUCED WHOLE OR IN PART, EXCEPT TO MEET THE SPECIFIC PURPOSE FOR WHICH IT WAS DEVELOPED.



# Engineering Load Data

## Design Criteria:

Code: ASCE 7-98

Wind Speed: 90MPH 3-Second Gust, 70mph sustained Exposure C

Nature of Occupancy: Type 1-Temporary Facility

## Notes:

External Guys to be installed at 45 degree from horizontal

Provide 1/4" cable cross bracing one end bay and every 6th bay as length requires.

Tent not to be located near abrupt changes in topography

Temporary Installation only ( $I=0.52$ )


Suspended Load: 3psf Projected on roof Maximum 200lbs point load

Soil conditions will vary from site to site. The included anchoring package for this tent may need to be supplemented with alternate anchoring during windy conditions and in areas with questionable soil holding power. The below chart lists the required resistance loads that must be supported by the anchoring system to meet the engineering loads specified under the code.

### Tectrac SK W/O Guys

### Tectrac SK W/ Guys

Width	(A) Uplift	(A) Shear		(B)Uplift w/HWK	(B) Shear w/HWK	(B) GUY Tension
20'x	70mph- 1110lbs	70mph- 1120lbs		N/A	N/A	N/A
30'x	70mph- 2420lbs	70mph-1600lbs		N/A	N/A	N/A
40'x	70mph- 3802lbs	70mph- 1800lbs		80mph- 4070lbs	80mph- 1610lbs	80mph- 4910lbs
50'x	N/A	N/A		70mph- 3490lbs	70mph- 700lbs	70mph- 3980lbs



# Parts Listing

Item	Item No.	Weight lbs	Item	Item No.	Weight lbs
TecTracSK Base Pl. w/Shackles	Z4040005	15	8x10 SK Gbl Wall 1pc FW	Z405GW08101PCFW	14
TecTracSK Base Insert Side	Z4040010	5	8x10 SK Gbl Wall 1pc UW	Z405GW08101PCUW	14
TecTracSK Base Insert Gable	Z4040015	5	8x10 SK Gbl Wall 2pc FW	Z405GW08102PCFW	14
TecTracSK EndCol Top Ins 5'-2"	Z4040020	20	8x10 SK Gbl Wall 2pc UW	Z405GW08102PCUW	14
TecTracSK Leg 5'-7" Asy flared	Z4040025	23	8x15 Left SK Gbl Wall 1pc FW	Z405GW0815L1PCFW	21
TecTracSK Str 10'-7 3/4" Plain	Z4040030	33	8x15 Left SK Gbl Wall 1pc UW	Z405GW0815L1PCUW	21
TecTracSK Str 5'-3 7/8" Assy	Z4040035	22	8x15 Left SK Gbl Wall 2pc FW	Z405GW0815L2PCFW	21
TecTracSK 5'-3 7/8" Asy w/Brkt	Z4040040	24	8x15 Left SK Gbl Wall 2pc UW	Z405GW0815L2PCUW	21
TecTracSK Str 5'-3 7/8" Plain	Z4040045	17	8x15 Right SK Gbl Wall 1pc FW	Z405GW0815R1PCFW	21
TecTracSK Eave Beam Assy.	Z4040050	36	8x15 Right SK Gbl Wall 1pc UW	Z405GW0815R1PCUW	21
TecTracSK Apex Beam Assy.	Z4040055	32	8x15 Right SK Gbl Wall 2pc FW	Z405GW0815R2PCFW	21
TecTracSK Purlin 10' Hinged	Z4040060	22.5	8x15 Right SK Gbl Wall 2pc UW	Z405GW0815R2PCUW	21
TecTracSK Purlin 15' Hinged	Z4040065	31.75	8x20 SK Gbl Wall 1pc FW	Z405GW08201PCFW	28
TecTracSK Purlin 20' Hinged	Z4040070	84	8x20 SK Gbl Wall 1pc UW	Z405GW08201PCUW	28
TecTracSK Kedar Purlin 10'	Z4040075	25.8	8x20 SK Gbl Wall 2pc FW	Z405GW08202PCFW	28
TecTracSK Kedar Purlin 15'	Z4040080	36.5	8x20 SK Gbl Wall 2pc UW	Z405GW08202PCUW	28
TecTracSK Kedar Purlin 20'	Z4040085	96.6	8x20 Left SK Gbl Wall 1pc FW	Z405GW0820L1PCFW	28
TecSK Cbl Lwr 1/4"x12'-6" 10'B	Z4040090	10	8x20 Left SK Gbl Wall 1pc UW	Z405GW0820L1PCUW	28
TecSK Cbl Lwr 1/4"x16'-8" 15'B	Z4040095	10	8x20 Left SK Gbl Wall 2pc FW	Z405GW0820L2PCFW	28
TecSK Cbl Lwr 1/4"x20'-11" 20B	Z4040100	10	8x20 Left SK Gbl Wall 2pc UW	Z405GW0820L2PCUW	28
TecSK Cbl Upr 1/4"x21'-11" 20x	Z4040105	10	8x20 Right SK Gbl Wall 1pc FW	Z405GW0820R1PCFW	28
TecSK Cbl Upr 1/4"x24'-9" 30x	Z4040110	11	8x20 Right SK Gbl Wall 1pc UW	Z405GW0820R1PCUW	28
TecSK Cbl Upr 1/4"x25'-3" 40x	Z4040115	12	8x20 Right SK Gbl Wall 2pc FW	Z405GW0820R2PCFW	28
TecSK Cbl Mdl 1/4"x22'-0" 50x	Z4040120	10	8x20 Right SK Gbl Wall 2pc UW	Z405GW0820R2PCUW	28
TecSK Cbl Lwr Ext 1/4"x10 1/8"	Z4040125	2	8x25 Left SK Gbl Wall 1pc FW	Z405GW0825L1PCFW	36
TecSK Asy Cbl 1/4"x18'-8" 20x	Z4040130	4	8x25 Left SK Gbl Wall 1pc UW	Z405GW0825L1PCUW	36
TecSK Asy Cbl 1/4"x28'-8" 30x	Z4040135	4	8x25 Left SK Gbl Wall 2pc FW	Z405GW0825L2PCFW	36
TecSK Asy Cbl 1/4"x38'-8" 40x	Z4040140	5	8x25 Left SK Gbl Wall 2pc UW	Z405GW0825L2PCUW	36
TecSK Asy Cbl 1/4"x48'-8" 50x	Z4040145	5	8x25 Right SK Gbl Wall 1pc FW	Z405GW0825R1PCFW	36
TecTracSK Leg Ext 2' Assy	Z4040150	12	8x25 Right SK Gbl Wall 1pc UW	Z405GW0825R1PCUW	36
TecSK 2'Adj. Base Ins 2' Side	Z4040155	20	8x25 Right SK Gbl Wall 2pc FW	Z405GW0825R2PCFW	36
TecSK 2'Adj. Base Ins 2' Gbl	Z4040160	20	8x25 Right SK Gbl Wall 2pc UW	Z405GW0825R2PCUW	36
*10x TectracSK Beam Cover UW	Z40310BCUW	9	10x10 SK Gbl Wall 1pc FW	Z405GW10101PCFW	16
*10x TectracSK Gable End UW	Z40310GPUW	30	10x10 SK Gbl Wall 1pc UW	Z405GW10101PCUW	16
*10x10 TectracSK Main Panel UW	Z40310MP10UW	25	10x10 SK Gbl Wall 2pc FW	Z405GW10102PCFW	16
*10x15 TectracSK Main Panel UW	Z40310MP15UW	38	10x10 SK Gbl Wall 2pc UW	Z405GW10102PCUW	16
*10x20 TectracSK Main Panel UW	Z40310MP20UW	52	10x15 Left SK Gbl Wall 1pc FW	Z405GW1015L1PCFW	24
*20x TectracSK Beam Cover UW	Z40320BCUW	10	10x15 Left SK Gbl Wall 1pc UW	Z405GW1015L1PCUW	24
*20x TectracSK Gable End UW	Z40320GPUW	40	10x15 Left SK Gbl Wall 2pc FW	Z405GW1015L2PCFW	24
*20x10 TectracSK Main Panel UW	Z40320MP10UW	35	10x15 Left SK Gbl Wall 2pc UW	Z405GW1015L2PCUW	24
*20x15 TectracSK Main Panel UW	Z40320MP15UW	50	10x15 Right SK Gbl Wall 1pc FW	Z405GW1015R1PCFW	24
*20x20 TectracSK Main Panel UW	Z40320MP20UW	65	10x15 Right SK Gbl Wall 1pc UW	Z405GW1015R1PCUW	24
*30x TectracSK Beam Cover UW	Z40330BCUW	15	10x15 Right SK Gbl Wall 2pc FW	Z405GW1015R2PCFW	24
*30x TectracSK Gable End UW	Z40330GPUW	60	10x15 Right SK Gbl Wall 2pc UW	Z405GW1015R2PCUW	24
*30x10 TectracSK Main Panel UW	Z40330MP10UW	45	10x20 SK Gbl Wall 1pc FW	Z405GW10201PCFW	32
*30x15 TectracSK Main Panel UW	Z40330MP15UW	65	10x20 SK Gbl Wall 1pc UW	Z405GW10201PCUW	32
*30x20 TectracSK Main Panel UW	Z40330MP20UW	89	10x20 SK Gbl Wall 2pc FW	Z405GW10202PCFW	32
*40x TectracSK Beam Cover UW	Z40340BCUW	20	10x20 SK Gbl Wall 2pc UW	Z405GW10202PCUW	32
*40x TectracSK Gable End UW	Z40340GPUW	80	10x20 Left SK Gbl Wall 1pc FW	Z405GW1020L1PCFW	32
*40x10 TectracSK Main Panel UW	Z40340MP10UW	56	10x20 Left SK Gbl Wall 1pc UW	Z405GW1020L1PCUW	32
*40x15 TectracSK Main Panel UW	Z40340MP15UW	85	10x20 Left SK Gbl Wall 2pc FW	Z405GW1020L2PCFW	32
*40x20 TectracSK Main Panel UW	Z40340MP20UW	111	10x20 Left SK Gbl Wall 2pc UW	Z405GW1020L2PCUW	32
*50x TectracSK Beam Cover UW	Z40350BCUW	25	10x20 Right SK Gbl Wall 1pc FW	Z405GW1020R1PCFW	32
*50x TectracSK Gable End UW	Z40350GPUW	100	10x20 Right SK Gbl Wall 1pc UW	Z405GW1020R1PCUW	32
*50x10 TectracSK Main Panel UW	Z40350MP10UW	67	10x20 Right SK Gbl Wall 2pc FW	Z405GW1020R2PCFW	32
*50x15 TectracSK Main Panel UW	Z40350MP15UW	100	10x20 Right SK Gbl Wall 2pc UW	Z405GW1020R2PCUW	32
*50x20 TectracSK Main Panel UW	Z40350MP20UW	135	10x25 Left SK Gbl Wall 1pc FW	Z405GW1025L1PCFW	40
8x10 TectracSK MainWall 1pcFW	Z40508101PCFW	14	10x25 Left SK Gbl Wall 1pc UW	Z405GW1025L1PCUW	40
8x10 TectracSK MainWall 1pcUW	Z40508101PCUW	14	10x25 Left SK Gbl Wall 2pc FW	Z405GW1025L2PCFW	40
8x10 TectracSK MainWall 2pcFW	Z40508102PCFW	14	10x25 Right SK Gbl Wall 1pc UW	Z405GW1025R1PCUW	40
8x10 TectracSK MainWall 2pcUW	Z40508102PCUW	14	10x25 Right SK Gbl Wall 1pc UW	Z405GW1025R1PCUW	40
8x15 TectracSK MainWall 1pcFW	Z40508151PCFW	21	10x25 Right SK Gbl Wall 2pc FW	Z405GW1025R2PCFW	40
8x15 TectracSK MainWall 1pcUW	Z40508151PCUW	21	10x25 Right SK Gbl Wall 2pc UW	Z405GW1025R2PCUW	40
8x15 TectracSK MainWall 2pcFW	Z40508152PCFW	21			
8x15 TectracSK MainWall 2pcUW	Z40508152PCUW	21			
8x20 TectracSK MainWall 1pcFW	Z40508201PCFW	28			
8x20 TectracSK MainWall 1pcUW	Z40508201PCUW	28			
8x20 TectracSK MainWall 2pcFW	Z40508202PCFW	28			
8x20 TectracSK MainWall 2pcUW	Z40508202PCUW	28			
10x10 TectracSK MainWall 1pcFW	Z40510101PCFW	16			
10x10 TectracSK MainWall 1pcUW	Z40510101PCUW	16			
10x10 TectracSK MainWall 2pcFW	Z40510102PCFW	16			
10x10 TectracSK MainWall 2pcUW	Z40510102PCUW	16			
10x15 TectracSK MainWall 1pcFW	Z40510151PCFW	24			
10x15 TectracSK MainWall 1pcUW	Z40510151PCUW	24			
10x15 TectracSK MainWall 2pcFW	Z40510152PCFW	24			
10x15 TectracSK MainWall 2pcUW	Z40510152PCUW	24			
10x20 TectracSK MainWall 1pcFW	Z40510201PCFW	32			
10x20 TectracSK MainWall 1pcUW	Z40510201PCUW	32			
10x20 TectracSK MainWall 2pcFW	Z40510202PCFW	32			
10x20 TectracSK MainWall 2pcUW	Z40510202PCUW	32			

If YOU can IMAGINE it... WE can BUILD it

[www.aztectents.com](http://www.aztectents.com)

**Aztec Tents**

2665 Columbia Street  
Torrance, CA 90503  
Toll Free (800) 228-3687  
Fax (310) 381-0722